

Post Construction Clean

Maintaining Data Centre health following building work

Overview

8 Solutions provides two levels of Post Construction Clean: Builders Clean and an Enhanced Builders Clean. Both are intended to be carried out after the completion of either the build of an entire new Data Centre or an extension/enhancement to an existing facility.

The Builders Clean is a basic level service that prepares the environment for the next stage of the fit out, it is not intended to be in any way an ISO level clean.

The Enhanced Builders Clean will prepare the room for the next stage of readiness in preparation for final stage deployment.

Builders Clean

The Builders Clean regime will encompass the following:

- Focus on all areas from the subfloor to high levels
- Removal of all 'non-heavy' construction debris
- Dry clean to visual acceptability

Enhanced Builders Clean

The Enhanced Builders Clean regime will encompass the following:

- Focus on all areas from the subfloor to high levels
- Removal of all 'non-heavy' construction debris
- Wipe down of all exposed surfaces
- Dry clean to visual acceptance
- Vacuum floor surface

Service detail

Before beginning any work within the room/facility a thorough check is performed to identify all utilities including emergency power off switches, all fire detection devices, including those located in the ceiling and floor voids and to ensure that the fire suppression is de-activated. If the fire system cannot be deactivated all fire detection units will be covered with a protective shield and located as highlighted on a detailed plan prepared by the 8 Solutions team leader.

A daily health and safety methodology briefing will then be given to the team by the team leader and a risk assessment will be performed as part of the clean.

